

PARAMETERS

	CODE	XLH260	XLH360	XLH380
REGULATION				
Temperature set point	Set T	●		
Humidity set point	Set H	●		
Half dead band width for temperature	dbt	●	●	●
Half dead band width for humidity	dbH	●	●	●
Minimum temperature set point limit	LS	◆		◆
Maximum temperature set point limit	uS	◆		◆
Outputs activation delay at start up	odS	◆		◆
Anti-short cycle delay	Ac	●	●	●
Humidity regulation	tHu	◆	◆	◆
Minimum humidity set point limit	LSH	◆	◆	◆
Maximum humidity set point limit	uSH	◆	◆	◆
DISPLAY				
Measurement unit	cF	◆	◆	◆
Resolution for temperature	rES	◆	◆	◆
Resolution for humidity	rEH	◆	◆	◆
DEFROST				
Instrument actions at the end of the cycle	trc		◆	◆
Defrost type	tdf	◆	◆	◆
Defrost mode	EdF	◆	◆	◆
Set point for Smart Defrost	SdF	◆	◆	◆
Defrost termination temperature	dtE	◆	◆	◆
Interval between defrosts	idF	●	●	●
Duration of defrost	MdF	●	●	●
Display during defrost	dFd	◆	◆	◆
Defrost display time out	dAd	◆	◆	◆
Drain down time	Fdt	◆	◆	◆
First defrost after start up	dPo	◆	◆	◆
Humidity control during defrost	Hud	◆	◆	◆
FANS				
Fan operating mode	Fnc	◆	◆	◆
Interval between 2 cycles of change of air	rFi		◆	◆
Duration of cycle of change of air	rFd		◆	◆
ALARM				
Temperature alarm configuration	ALc	◆	◆	◆
Low temperature alarm setting	ALL	●	●	●
High temperature alarm setting	ALu	●	●	●
Temperature alarm recovery differential	ALH	◆	◆	◆
Temperature alarm delay	ALd	◆	◆	◆
Delay of temperature alarm at start-up	dAo	◆	◆	◆
Alarm delay at the end of defrost	EdA	◆	◆	◆
Delay of temperature alarm after closing the door	dot	◆	◆	◆
Humidity alarm configuration	AHc	◆	◆	◆
Low humidity alarm setting	AHL	●	●	●
High humidity alarm setting	AHu	●	●	●
Humidity alarm recovery differential	AHH	◆	◆	◆
Humidity alarm delay	AHd	◆	◆	◆
Delay of humidity alarm at start-up	dHo	◆	◆	◆
Alarm delay at the end of defrost	doH	◆	◆	◆
Open door alarm delay	doA	◆	◆	◆
Max number of Pressure Switch activations	nPS	◆	◆	◆
ANALOG INPUT				
Thermostat probe calibration	Ot	●	●	●
Evaporator probe calibration	oE	◆	◆	◆
Humidity probe calibration	o3	●	●	●
Evaporator probe presence	P2P	◆	◆	◆
Humidity probe presence	P3P	◆	◆	◆
DIGITAL INPUT				
Readout at 4mA	Lci	◆	◆	◆
Readout at 20mA	uci	◆	◆	◆
Digital input polarity	i1P	◆	◆	◆
Digital input configuration	i1F	◆	◆	◆
Outputs status when open door	odc	◆	◆	◆
Outputs regulation restart after door open alarm	rrd	◆	◆	◆
Digital input alarm delay	did	◆	◆	◆
OTHER				
1 st relay configuration	oA1	◆	◆	◆
2 nd relay configuration	oA2		◆	◆
3 rd relay configuration	oA3		◆	◆
Serial address	Adr	◆	◆	◆
Map code	Ptb	◆	◆	◆
Software release	rEL	◆	◆	◆
Probe display	Prd	◆	◆	◆

● Present ◆ Present and password protected